

HOME RETROFIT SPECIFICATIONS MANUAL

HEAT PUMP WATER HEATER COMPLETE MEASURE CHECKLIST

All work must meet Energy Trust of Oregon specifications. **This checklist serves as a reference guide only.** Please refer to the current Specifications Manual for additional information and clarification. Specific reference sections are noted in italics.

<input type="checkbox"/> Condensate produced by the system is removed via an adequately sloped drainage system and flows to a suitable termination point. <i>IN 1.16</i>
<input type="checkbox"/> Unit location and clearances around the unit shall meet manufacturer requirements. <i>IN 1.14</i>
<input type="checkbox"/> Ducting and applicable fans settings shall be set in accordance with the manufacturer's specifications. <i>IN 1.14</i>
<input type="checkbox"/> If only exhaust air is ducted outside of conditioned space, contractor should ensure combustion appliances are functioning properly and safely and carbon monoxide alarm requirements are met. <i>IN 1.2</i>
<input type="checkbox"/> In jurisdictions where it is required, ensure heat pump water heater is strapped on the upper third and lower third of the tank to resist horizontal displacement caused by seismic motion. <i>WH 1.0</i>

Print Name:	Signature:	Date:
-------------	------------	-------